

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

AP. NUMBER 15-097-20-097-0000 ⁹⁰⁷

LEASE NAME Bransing

WELL NUMBER C#1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 3 TWP. 28 RGE. 20 (E) or (W)

COUNTY Kiowa

Date Well Completed 10-16-82

Plugging Commenced 9:35 4-10-86

Plugging Completed 10:30 4-10-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR J. Mark Richardson

ADDRESS 640 Century Plaza, Wichita, Kansas 67202

PHONE# (316) 262-3192 OPERATORS LICENSE NO. 5414

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #1

Is ACO-1 filed? yes If not, is well log attached?

Producing Formation N/A. Depth to Top 4896 Bottom 4899 T.D. 4910

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	598.0	0
				4 1/2	4909	1987.45

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom plug 1 hull, 30 sks. com. cement to 4800' 200 PSI max.
200 ISIP Top plug 3 hull, 10 gel, 50 sks 40/60 pox. 10 gel, 1 Hull
8 5/8 plug 125 sks 40-60 pos. mix. pumped 10 sks cement in water well max
press. 800 PSI = ISIP 600 PSI
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 768, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

Randy P. Wagner (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Randy P. Wagner

(Address) Box 768, Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 15th day of April, 1986

Lovella L. Mullen
Notary Public

My Commission Expires: 1-13-90



RECEIVED
STATE CORPORATION COMMISSION

APR 16 1986

Form CP-4
Revised 08-84

CONSERVATION DIVISION
Wichita, Kansas

GAUBERT-JONES, INC.
WICHITA, KANSAS

15-097-20907-0000

DRILLERS WELL LOG

BREWSING "C" #1
NW 1/4 NW Sec. 3-28S-20W
Kiowa County, Kas.

Commenced: 10/4/82
Completed: 10/16/82

OPERATOR: J. PARK RICHARDSON

Depth: From	To	Formation	Remarks
0	200	Sand-Clay	
200	608	Redbed	Run 14 Jts. of 24# 8 5/8" csg. set @ 598' cemented w/175 sx. annon 2% Gel
608	2124	Shale	2% CC + 200 sx Lite 2% Gel
2124	2755	Shale-Lime	3% CC - P.D. @ 7:00 PM 10/16/82
2755	2896	Lime-Shale	10-4-82
2896	3020	Shale-Lime	
3020	4910	Lime	
4910' T.D.			Run 122 Jts. of 10# 9 1/2" 4-1/2" Csg. set @ 4909' cemented w/200 sx. 60/40 possible 2% Gel - 3/4 of 1% CFR 2 P D @ 6:00 PM 10/16/82

State of Kansas }
COUNTY OF SEDWICK }

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GAUBERT-JONES, INC.

James S. Sutton
James S. Sutton, II

Subscribed and sworn to before me
this 21st day of October, 1982.

Lola L. Costa
Lola L. Costa - Notary Public

My Commission expires November 21, 1994.



STATE COMMISSION

MAR 18 1985

CONSERVATION DIVISION
Wichita, Kansas