


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Kiowa County. Sec. 1 Twp. 28S Rge. 20W (EX) (W)  
Location as "NE/CNW/SW" or footage from lines C SE SE  
Lease Owner D. R. Lauck Oil Company, Inc. & Sun Oil Company  
Lease Name Sherer Well No. 1  
Office Address 301 S. Broadway, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 6, 19 65  
Application for plugging filed July 6, 19 65  
Application for plugging approved July 6, 19 65  
Plugging commenced July 6, 19 65  
Plugging completed July 6, 19 65  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Ewing  
Producing formation -- Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4950 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	318'	8-5/8"	318'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole filled with mud 4950'-275'  
Plug 275'-271'  
25 sacks Cement 271'-40'  
Cement 40'-6' Bottom of cellar

RECEIVED  
STATE CORPORATION COMMISSION

JUL 14 1965  
7-14-65  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Lauck Drilling Company, Incorporated  
Address 301 S. Broadway, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
John H. Knightley (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Knightley  
301 S. Broadway, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of July, 19 65  
Stella J. Lippie  
Notary Public.

My commission expires March 12, 1967

15-097-30018-0000

D. R. Lauck Oil Company, Inc. and  
Sun Oil Company

Sherer #1

C SE SE Sec. 1-28S-20W  
Kiowa County, Kansas

Commenced: June 23, 1965  
Completed: July 6, 1965

Casing Record: 317' 8-5/8" Cemented with 265 sacks Cement,  
2% Calcium Chloride.

Elevation: 2292 GL; 2295 DF; 2297 KB.

Drillers Log

Tops

Sand	156
Red Bed	250
Blue Shale	318
Shale	515
Sand	590
Sand & Shale	680
Sand	695
Gypson	710
Red Bed & Shells	1615
Shale & Shells	2115
Shale & Anhydrite	2415
Shale & Lime	2515
Lime & Shale	2625
Lime	2735
Lime & Shale	2865
Shale & Lime	3290
Lime & Shale	3390
Shale & Lime	3540
Shale, Lime & Chalk Streaks	3708
Broken Lime & Chalk Streaks	3860
Lime	3940
Shale & Lime	4040
Lime & Chalk	4121
Lime & Shale	4220
Shale & Lime	4330
Lime	4898
Lime & Miss.	4917
Lime, Chert & Shale	4950 RTD

	Samples	Electra
Heebner	4134-1837	4132-1835
Toronto	4147-1850	4152-1855
Douglas	4272-1975	4272-1975
Brown Lime	4288-1991	4288-1991
Lansing	4296-1999	4296-1999
Base Kansas City	4690-2393	4690-2393
Marmaton	4700-2403	4700-2403
Cherokee Shale	4827-2530	4827-2530
Mississippian	4904-2607	4902-2605
Total Depth	4950-2653	4949-2652

DST #1 (S) 4904-4917, open 1 hour with good blow 1 hour. Recovered 360' gas in pipe, 60' very slightly oil and gas cut mud, 30' slightly gas-cut mud, 240' muddy water.

ISIP 1380#, 30 minutes  
 FSIP 1363#, 30 minutes  
 IFP 33#  
 FFP 142#

D&A

RECEIVED  
STATE CORPORATION COMMISSION

JUL 14 1965

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that this is a true and correct log of the above mentioned well, to the best of my knowledge and belief.

*John H. Knapp*  
Subscribed and sworn to before me this

13<sup>th</sup> day of July 1965

*Stella J. Lippa*  
Notary Public

My commission expires 3-12-67