

API NUMBER Drill 1958

LEASE NAME Toner

WELL NUMBER 1

C SE NW ft. from S Section Line

         ft. from E Section Line

SEC. 24 TWP. 28 SRGE. 21 ~~XX~~ (W)

COUNTY Ford

Date Well Completed 12-1958

Plugging Commenced 10-2-91

Plugging Completed 10/11/91

TYPE OR PRINT  
 NOTICES: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Graham Michaelis Corporation

ADDRESS P.O. Box 247, Wichita, KS 67201

PHONE#(316) 264-8394 OPERATORS LICENSE NO. 5134

Character of Well Gas

(Oil, Gas, DIA, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dodge City

Is ACO-1 filled? x If not, is well log attached? x 10-23-91

Producing formation x Depth to Top          Bottom          T.D. 5155

Show depth and thickness of all water, oil and gas formations.

RECEIVED  
 STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASINO RECORD

Formation	Content	From	To	Size	Put in	Pulled out	OCT 23 1991
				8 5/8	413	225sx none	
				5 1/2	5154	3000	WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 100 feet to          feet each set. 300 hulls, 15 jell, 50 cement, 10 jell, 100 hulls, 8 5/8" wiper plug; 175 sacks of cement pump in surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

STATE OF Kansas COUNTY OF Barber, ss.

Jeff Sletto (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jeff Sletto

(Address) Medicine Lodge, Ks

State of Kansas - Notary Public

GLENDA MORRISON

SUBSCRIBED AND SWORN TO before me this 11 day of October, 19 91

My Appt. Exp. 5-17-94

Glenda Morrison  
 Notary Public

My Commission Expires 5-17-94

Pumped 20 SX cement in 4" water well csg to fill from top to bottom  
 OCT 17 1991

**GRAHAM-  
MICHAELIS  
DRILLING COMPANY**

WILLIAM L. GRAHAM

W. A. MICHAELIS, JR.

HOBERT 4-8394

15-057-10004-0000

GRAHAM BUILDING • 211 NORTH BROADWAY • WICHITA 2, KANSAS

COMPLETION REPORT

TONER #1

LOCATION: C SL NW - Sec. 24-28-21W  
Ford County, Kansas

CASING RECORD: 8 5/8" @ 413 w/225 sx  
5 1/2" @ 5154 /150 sx

TOTAL DEPTH: 5155' RTD

ELEVATION: 2395 KB

Dec. 29, 1958 Moved in cable tool unit #1. Rigged up & swabbed hole down. Frontier ran collar log. TD 5104'.

Dec. 30, 1958 Perforated from 5048-5060 - 4 H.P.F. In 1 hour well gauged 4,500 MCFG & wet. After 9 hrs. well gauged 4,500. Shut well for 4 hrs. Rock pressure 1310#. Shut down rig, waiting on tubing.

Jan. 2, 1959 Shut in pressure 1310.2 hr. blowdown 5,400 MCFG. Ran 80 jts 2" 10 rd thd reg tubing with 14' mud anchor on bottom & 84 jts 2" 8rd thd EUE J-55 tubing with 1-2" x 10' tubing sub. Total 5062'. Tubing perfs - 5050-5055. Bottom of tubing at 5065'.

Jan. 13, 1959 4 - pt. back pressure test  
6613 mcf/d.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 30 1991

Corporation Division  
Wichita, Kansas