

State of Kansas



FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 28 1964  
08-28-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Jack Beck of Phillips Petroleum Company has this date requested permission to plug the following described well:

Mr. Beck guarantees payment of the plugging fee.

Operator's full Name: Phillips Petroleum Company

Complete Address: Box 287, Great Bend, Kansas

Lease Name: Thompson "J" Well No. # 1

Location: C NE NW Sec. 35 Twp. 29 Rge. 11 (E) (W) W

County Pratt Total Depth 480' ~~380'~~ Oil Well       

Gas Well        Input Well        SWD Well        D & A X Lost Hole       

Mr. Beck was instructed to plug the well as follows:

358' of 8 5/8" surface pipe, cemented with 160 sacks. Fill hole with drilling mud to 300', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,  
*Archie Clewing*