

State of Kansas



FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 15 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Clyde Merkle of Lauck Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Merkle guarantees payment of the plugging fee.

Operator's full Name: D. R. Lauck Oil Company, Inc.

Complete Address: 301 S. Broadway, Wichita, Kansas

Lease Name: Knop Well No. # 1

Location: C NW SE Sec. 22 Twp. 29 Rge. 11 (E) (W) W

County Pratt Total Depth 4775' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Merkle was instructed to plug the well as follows:

269' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fill with drilling mud to 240', 1st cementing plug, bridge with 1/4 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/4 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,
Archie Elving