



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 3 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Frank Musgrove of Hellar Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Kern-Landes Exploration Company Inc.,

Complete Address: Box 107, Liberal, Kansas

Lease Name: Pitzer Well No. # 1

Location: C NW SE Sec. 22 Twp. 29 Rge. 13 (E) (W) W

County Pratt Total Depth 4728 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

303' of 10 3/4" surface pipe, cemented with 250 sacks. Fill hole with drilling mud to 225', 1st cementing plug, bridge with hulls, and cement with 30 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 15 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent