

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1970
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202Operator's Full Name Bachus Oil Co.Complete Address 721 E. Central Wichita, KsLease Name Knop Well No. 3Location NE/NE/SW Sec. 22 Twp. 29 Rge. 11 (E) (W) WCounty Pratt Total Depth 4824Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated Plugging Contractor Clarke Oilfield Service Inc.Address Chapin Bldg. Medicine Lodge, Ks License No. 583Operation Completed: Hour 9:AM Day 28 Month 10 Year 1970

The above well was plugged as follows:

366 ft of 8 5/8 surface pipe cemented with 255 sacks. 4665 ft of 5 1/2
long string cemented with 175 sacks. Open hole. Sand back to 4500 ft.
5 sacks cement with bailer. Pulled 3100 ft of 5 1/2. Set 10 ft rock
bridge at 270 ft. Fill hole with 4 1/2 yds of redimix. to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. Russell Bihler
Well Plugging Supervisor

INVOICED

DATE 10-30-70INV. NO. 2785-W