

f

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name F. G. Holl.  
Complete Address 6427 E. Kellogg, Wichita, Ks. 67207  
Lease Name Miller Well No. 2-20  
Location 50' E W/2 SW SE Sec. 20 Twp. 29s Rge. 11 (E)    (W) X  
County Pratt Total Depth 2815  
Abandoned Oil Well    Gas Well X Input Well    SWD Well    D & A     
Other well as hereafter indicated     
Plugging Contractor Kelso Casing Pulling.  
Address Box 176-Chase, Ks. 67524 License No. 683  
Operation Completed: Hour 3:30 Pm. Day 27 Month 8 Year 1979

The above well was plugged as follows:

261' 7" casing. 4 1/2" casing set at 2814' w/75 sax cement. Preforated  
at 2754'-Sand back to 2700'-Top sand w/4 sax mixed cement w/dump bailer  
Pull 2075' 4 1/2" casing. Sun mixed & pumped 8 sax hulls-25 sax gel-  
Release plug-Mixed & pumped 75 sax 50/50 posmix cement w/4% gel & 3%  
cc to top of casing. Shut in w/300# pressure.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 30 1979

8-30-79  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

OICED

9-5-79

INV. NO. 0339-W