

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev.03/92

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-057-20,534-~~000~~ (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Cross Bar Petroleum, Inc. KCC LICENSE # 4243  
(owner/company name) (operator's)

ADDRESS 151 N. Main, Suite 630 CITY Wichita

STATE KS ZIP CODE 67202-1407 CONTACT PHONE # (316) 265-2279

LEASE Hubbell WELL# 1-2 SEC. 2 T. 28S R. 21 (East/West)

50'E of S/2 NE NW SPOT LOCATION/0000 COUNTY Ford

4290 FEET (in exact footage) FROM (S) (circle one) LINE OF SECTION (NOT Lease Line)

2030 FEET (in exact footage) FROM (W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8-5/8"25# SET AT 602' CEMENTED WITH 375 SACKS

PRODUCTION CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: None

ELEVATION 2347' / 2358' T.D. 5080' PBSD \_\_\_\_\_ ANHYDRITE DEPTH 1339' (+1019)  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING On 4-13-95, Bill Wynn discussed w/ Steve Durrant, KCC Dist #1.

135 sx 60/40 Pozmix w/ 6% Gel as follows: 1st plug @ 1380' w/ 50 sx, 2nd plug @ 630' w/

50 sx, 3rd plug @ 40' w/ 10 sx & wood plug, Rathole 15 sx & Mousehole 10 sx.  
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bill Wynn - Toolpusher, Rig #21 PHONE# (913) 462-7541

ADDRESS PO Box 661 City/State Colby, KS 67701-0661

PLUGGING CONTRACTOR Murfin Drilling Co., Inc. KCC LICENSE # 30606

ADDRESS 250 N. Water, #300, Wichita, KS 67202 PHONE # (316) 267-3241  
(company name) (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (if known?) 3 P. RECEIVED  
4-14-95

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 5-10-95 AUTHORIZED OPERATOR/AGENT: C. K. Morrison

C. K. Morrison, Operations Manager

5-1-95