

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued February 14, 1968.

RECEIVED
STATE CORPORATION COMMISSION
FEB 19 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Misco Leasing, Inc.

Complete Address: 101 Misco Bldg., Wichita, Kansas 67202

Lease Name Cook Well No. # 1

Location C SE SW Sec. 25 Twp. 28 Rge. 15 (E) (W) W

County Pratt Total Depth 4748'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas 67578 License No. 490

Operation Completed: Hour 2:45PM Day 17th Month February Year 1968

The Above well was plugged as follows:

325' of 8 5/8" surface pipe, cemented with 275 sacks. 4610' of 4 1/2" long string,
cemented with 100 sacks. Top perferation 4531'. 100 sacks of cement was pumped
on bottom, with the top of the cement at 4003'. 3260' of 4 1/2" long string was
recovered from the hole. Fluid level in the hole was at 280', bridge plug and
rock bridge from 280' to 270', and hole was filled with 4 yards of ready-mix,
cement with cement from 270' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Audie Elving
Well Plugging Supervisor

INVOICED
DATE - 2/19/68
INV. NO. 7286-4