

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAY 7 1963

CONSERVATION DIVISION  
Wichita, KansasJ. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name J. E. Newman

Complete Address: Suite 2005 Tower Bldg., Denver 2, Colorado

Lease Name Thompson Well No. # 1

Location NE NE NW Sec. 22 Twp. 28 Rge. 15 (E) (W) W

County Pratt Total Depth 4576

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Cherokee Drilling Co.

Address: Suite 2005 Tower Bldg., Denver 2, Colo. License No. 350

Operation Completed: Hour 6:30PM Day 3rd Month May Year 1963

The Above well was plugged as follows:

289' of 8 5/8" surface pipe, cement circulated. 4576' of 5 1/2" long string,  
cemented with 150 sacks. perforated 4528 to 33'. Sanded to 4501', cement-  
ed with 6 sacks. Plug was set at 225', 10' rock bridge, fluid in hole  
was bailed down, and plug was cemented with 20 sacks. Hole filled with  
mud to 40', 10' rock bridge, cemented with 10 sacks to base cellar.  
2810' of 5 1/2" long string recovered from hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/9/63

INV. NO. 7022-4

Signed: Archie Elving  
Well Plugging Supervisor