

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT **RECEIVED**
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

MAY 18 1965
05-18-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Burch Exploration, Inc., & National Associated Petroleum

Complete Address: 1011 Union Center, Wichita, Kansas

Lease Name Hearn Well No. # 1

Location C SE NW Sec. 5 Twp. 29 Rge. 12 (E) (W) W

County Pratt Total Depth 4670'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Vaughan Drilling, Inc.

Address: Box 825, Great Bend, Kansas License No.

Operation Completed: Hour 1:00 PM Day 17th Month May Year 1965

The Above well was plugged as follows:

350' of 8 5/8" surface pipe, cement circulated with 300 sacks. Fluid level in the hole was at 165'. 1st cementing plug and 1/2 sack of hulls was pushed in fluid to 300', and cemented with 25 sacks, through the drill pipe. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged solid with dry cement and hulls on fluid at 40', and cemented with 10 sacks to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/18/65

INV. NO. 1173-W