

15-095-00322-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pratt County, Sec. 30 Twp. 27S Rge. 9 (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW
Lease Owner Cooperative Refinery Assn.
Lease Name Sheldon "C" Well No. 1
Office Address 911 Central Bldg-Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 8-29 1952
Application for plugging filed 8-29 1952
Application for plugging approved 19
Plugging commenced 8-29 1952
Plugging completed 9-12 1952
Reason for abandonment of well or producing formation Dry Hole

NORTH

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation ash Depth to top _____ Bottom _____ Total Depth of Well 4402 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3990'	3139'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

L-W Plug at 4000'
Filled with sand 4000 - 3970
Cement 6 Sacks
Mudded
Rock bridge @ 220' Cement 25 sacks
Mudded - Rock bridge 20-10'
Cement 5 sacks

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Betts Oil Field Service
Address Gorham, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jack R. Jones (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack R. Jones

(Address)

SUBSCRIBED AND SWORN TO before me this 14 day of October, 1952

My commission expires May 5, 1953

24-2675-S 2-52-20M

Ruel Durkee
Notary Public.
STATE CORPORATION COMMISSION

OCT 15 1952 10-15-52

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 30 27S R. 9
BOOK PAGE 41 LINE 17

COPY


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- COOPERATIVE REFINERY ASSOCIATION
Farm- Sheldon "C" No. 1

SEC. 30 T. 27 R.9 W
SE SE SW

Total Depth. 4486
Comm. 6-18-52 Comp. 8-27-52
Shot or Treated.
Contractor. Kaufman
Issued. 10-25-52

County Kingman
KANSAS



Elevation. 1660 D.E.

Production. dry

CASING:

8 5/8" 274' cem w/175 sx
5 1/2" 4400' cem w/125 sx

Figures Indicate Bottom of Formations.

surface clay, sand	70
red bed, shale	460
shale, shells	1350
salt, shale, shells	1505
lime	1680
lime, shale	3435
lime	3475
lime, shale	3525
lime	3740
lime, shale	3780
lime	3835
lime, shale	3905
lime	3940
lime, shale	3990
lime	3996
lime cherty	4060
lime, shale	4140
shale	4200
shale, lime	4240
shale	4275
dolomite, chert	4373
sand, lime, shale	4405
shale, lime	4460
lime arbuckle	4486
Total Depth. RTD	

Tops:

Lansing	3642-44
Mississippi chert	3980-92
Viola	4283-89
Simpson sand	4361-76
Arbuckle	4451-86

RECEIVED
STATE CORPORATION COMMISSION

MAY 12 1966

12 11 1966
Wichita, Kansas