


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County. Sec. 35 Twp. 27S Rge. 8W EXX
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____

C - SE NE
Lease Owner Publishers Petroleum
Lease Name O. S. Osner Well No. 1
Office Address P. O. Box 25125, OK City, OK 73125
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Dry Hole
Date Well completed April 20, 1978
Application for plugging filed Verbal Application 19____
Application for plugging approved Verbal Approval 19____
Plugging commenced April 20, 1978
Plugging completed April 20, 1978
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,996
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	350'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,996 ft. (rotary total depth) to 360 ft. Set plug at 360 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 360 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 12 sacks cement, 3 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Services Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this form)
Name of Plugging Contractor Halliburton Services
410 Union Center Bldg., Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1978
4-26-78

STATE OF Kansas COUNTY OF Sedgwick
Dean Britting, Agent (employee of owner) XXXXXX (owner or operator) XXXXXX

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 N. Main, Wichita, Kansas 67202
(Address)

ELsie Willison
NOTARY PUBLIC
WICHITA, KANSAS
SUBSCRIBED AND SWORN TO before me this 25th day of April, 1978

My commission expires June 30, 1978
Elsie Willison
Elsie Willison - Notary Public.

KANSAS DRILLERS LOG

COMPANY Publishers Petroleum
 FARM O. S. Osner NO. 1

SEC. 35 T. 27S R. 8W
 LOC. C - SE 1/4

COUNTY Kingman

ROTARY TOTAL DEPTH 3,996'
 COMM. April 11, 1978
 CONTRACTOR H-30, Inc.
 ISSUED April 25, 1978

COMP. April 20, 1978

CASING

10 3/4"
 8 5/8" Set at 350' cemented w/300 sxs cement
 5 1/2"
 4 1/2"

ELEVATION 1,609 GR.

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Red Bed	352'
Red Bed	550'
Shale	1,190'
Shale and Lime	1,540'
Lime and Shale	3,780'
Lime	3,867'
Lime and Shale	3,996'
Rotary Total Depth	3,996'

RECEIVED
 STATE CORPORATION COMMISSION

APR 26 1978

CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting

 Dean Britting

State of Kansas }
 County of Sedgwick } SS:

Suscribed and Sworn to before me a Notary Public in and for said county and state this 25th day of April, 1978.



Elsie Willison

 Elsie Willison - Notary Public

My Commission Expires:
 June 30, 1978