


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Kiowa County. Sec. 33 Twp. 27 Rge. 16 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

C SE NW  
Lease Owner Mark Richardson  
Lease Name Davis #3 Well No.  
Office Address Wichita, Kansas  
Character of Well (Completed as Oil, Gas or Dry Hole)



Date Well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 5/28/76 19  
Plugging completed 6/3/76 19  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein  
Producing formation Depth to top Bottom Total Depth of Well 4775  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	FEET IN	PULLED OUT
				8-5/8	278	none
				4 1/2"	4774	3007'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded to 4700' and ran 4 sacks cement. Loaded hole, worked pipe to 16" tension. Loaded hole and shot pipe at 3002', pulled 89 joints. Bailed fluid down to 240' and set rock bridge with 4 yards ready mix.

PLUGGING COMPLETE.

JUN 07 1976

CONSERVATION DIVISION  
Wichita, Kansas

6-7-76

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE  
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS (Address)

Subscribed and sworn to before me this 4th day of June 1976

My commission expires  
NOTARY PUBLIC  
MARGARET MELCHER  
Rice County, Ks.  
My Comm. Exp. Feb. 15, 1979

Margaret Melcher  
Notary Public

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

DAVIS #3  
 C SE NW Section 33-27S-16W  
 Kiowa County, Kansas

Commenced: July 14, 1969  
 Completed: July 25, 1969

OPERATOR - J. Mark Richardson

RECEIVED  
 STATE COMMISSION  
 MAY 04 1970  
 CONSTRUCTION DIVISION  
 Kansas

DEPTH		FORMATION	REMARKS
From	To		
0	160	Surface clay, sand, shells	
160	200	Sand	
200	910	Shale and red bed	Ran 11 joints of 8-5/8" casing, set @ 275' w/250 sacks cement.
910	1048	Red bed	
1048	1065	Anhydrite	
1065	2200	Shale and shells	
2200	4090	Lime and shale	
4090	4620	Lime	
4620	4625	Lime and sand	
4695	4775	Lime	
4775	TD		Ran 143 joints of 4-1/2" casing, set @ 4479' w/400 sacks cement.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C SE NW Section 33-27S-16W, Kiowa County, Kansas, to the best of my knowledge and belief.

*E. E. Hall*  
 \_\_\_\_\_  
 E. E. HALL

STATE OF KANSAS        )  
                                   )  
 COUNTY OF SEDGWICK    )

Before me, the undersigned, a Notary Public within and for said County and State, on this 29 day of July, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972.

*Barbara J. Layton*  
 \_\_\_\_\_  
 Barbara J. Layton, Notary Public

