


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Kiowa County, Sec. 33 Twp. 27 Rge. (E) 16 (W)
Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner Rosen Oil Co.
Lease Name Davis Well No. 3
Office Address 260 Sutton Place - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Jan. 3, 19 69
Application for plugging filed (letter 1-13-69) Jan. 3, 19 69
Application for plugging approved Jan. 3, 19 69
Plugging commenced Jan. 3, 19 69
Plugging completed Jan. 3, 19 69
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4750 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	266'	8-5/8"	266'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 600 feet. Set first plug @ 600 feet with 75 sacks cement. Filled hole with heavy mud to 250 feet. Set second plug @ 250 feet with 25 sacks cement. Filled hole with heavy mud to 40 feet. Set third plug @ 40 feet with 10 sacks cement. Plug rat hole with 2 sacks cement. Hole plugged using pump truck, pumping through drill pipe. Job complete @ 9:30 AM, January 3, 1969.

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place - Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. E. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall
830 Sutton Place - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13 day of January, 19 69

Barbara J. Layton
Barbara J. Layton Notary Public.



GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

DAVIS #3
C NE SW Section 33-27S-16W
Kiowa County, Kansas

Commenced: December 17, 1968
Completed: January 3, 1969

OPERATOR - Rosen Oil Company

DEPTH	FORMATION	REMARKS
From To		
0 266	Surface clay, sand and shale	Ran 12 joints of 8-5/8" casing set @ 266' w/215 sacks cement.
266 1040	Red bed	
1040 1065	Anhydrite	
1065 2155	Shale and shells	
2155 4200	Lime and shale	
4200 4565	Lime	
4564 4645	Lime and shale	
4645 4685	Lime	
4685 4735	Lime and chert	
4735 4750	Lime	
4750 TD		Dry and abandoned.

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1969
CONSERVATION DIVISION
Wichita, Kansas

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C NE SW Section 33-27S-16W, Kiowa County, Kansas, to the best of my knowledge and belief.

E. E. Hall

E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 13th day of January 13, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972

Barbara J. Layton
Barbara J. Layton, Notary Public

