


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
11 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kiowa County, Sec. 35 Twp. 27 Rge. 16 (X) (W)
Location as "NE/CNW/SW" or footage from lines G NE NE
Lease Owner Bowers Drilling Company, Inc.
Lease Name Horton Well No. 1
Office Address 416 Union Center Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-12-62 19
Application for plugging filed 11-12-62 19
Application for plugging approved 11-12-62 19
Plugging commenced 11-12-62 19
Plugging completed 11-12-62 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, verbally

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4800 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud to 325'
Set first plug at 325' w/20 sacks cement
Filled with heavy mud to 35'
Set second plug at 35' with 10 sacks cement
2 sacks in rathole

RECEIVED
STATE CORPORATION COMMISSION
NOV 23 1962
CONSERVATION DIVISION
Wichita, Kansas

11-26-62

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Bowers Drilling Company, Inc.
Address 416 Union Center Building

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bauer
416 Union Center Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of November, 1962

Hanna F. Miller
Notary Public.

My commission expires May 1, 1966



WELL LOG

COMPANY: Bowers Drilling Company, Inc.
 CONTRACTOR: Bowers Drilling Company, Inc.
 FARM: Horton #1
 LOCATION: C NE NE Section 35-27-16
 Kiowa County, Kansas

COMMENCED: 10-28-62
 COMPLETED: 11-12-62
 ELEVATION: 2111 K.B.

0	-	35	Sand and clay
35	-	350	Sand and Shale
350	-	1020	Redbed and Shale
1020	-	1038	Anhydrite
1038	-	1285	Shale
1285	-	1800	Shale and Shells
1800	-	4410	Lime and Shale
4410	-	4480	Lime
4480	-	4650	Lime and Shale
4650	-	4660	Lime
4660	-	4755	Lime and Chert
4755	-	4800	Lime and Shale Chert
4800	-		T. D.

8-5/8" casing set at 349'

LOG TOPS:

Heebner	3946	Lansing	4128	Cherokee Sand	4588
Toronto	3968	Base K. C.	4438	Mississippian	4624
Douglas	3998	Marmaton	4453	Kinderhook Sand	4688
Brown Lime	4110	Cherokee Shale	4566	Viola	4748

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the Horton #1, C NE NE, Section 35-27-16, Kiowa County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

Emil E. Bowers
 Emil E. Bowers

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 21st day of November, 1962.

Donna F. Miller
 Donna F. Miller, Notary Public

My commission expires May 1, 1966

RECEIVED
 STATE CORPORATION COMMISSION

NOV 27 1962

CONSERVATION DIVISION
 Wichita, Kansas