


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

X& Kiowa County. Sec. _____ Twp. 25 Rge. 27 (E) 16 (W)
Location as "NE/CNW&SW&" or footage from lines C SE SW
Lease Owner Pawnee Petroleum Company, Inc.
Lease Name Burns Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1-2-62 _____ 19____
Plugging completed: 1-9-62 _____ 19____
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hample
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4860' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	333'	None
				5-1/2"	4802'	2879'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4625', sanded to 4220' and dumped 4 sacks of cement @ 4220' with dump bailer. Pulled 5 1/2" casing. Set 10' rock bridge from 310' to 300' and ran 20 sacks of cement. Mudded to 40', set 10' rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1962

CONSERVATION DIVISION
Wichita, Kansas

4-26-62

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of January, 1962

My commission expires May 20, 1962

Milton J. Volini
Notary Public.



PAWNEE PETROLEUM COMPANY, INC.

1407 NORTH BATTIN

WICHITA 8, KANSAS

DRILLERS LOG

COMPANY: PAWNEE PETROLEUM Co., Inc.
LEASE: BURNS # 1
LOCATION: C SE SW 25-27S-16W
KIOWA COUNTY, KANS.

COMMENCED: 8-9-61
COMPLETED: 8-31-61
ELEVATION: G L 2097'
TOTAL DEPTH: 4860'

CONTRACTOR: CHEROKEE DRLG. & EXPLORATION Co. DENVER, COLO.

CASING: 333' (17 JTS) 8 5/8" 8 V THR 28 1/2# USED SURF CGG W/300 SX CEMENT
4802.86' 5 1/2" 8RD 14# SMLS USED W/200 SX CEMENT

0- 190 SAND - SHELLS
190 - 321 SHALE
321 - 970 SHALE & SHELLS
970 - 2310 SHALE & LIME
2310 - 2375 LIME
2375 - 2663 LIME & SHALE
2663 - 2930 SHALE & LIME
2930 - 3040 LIME & SHALE
3040 - 4142 SHALE & LIME
4142 - 4625 LIME
4625 - 4650 SAND & SHALE
4650 - 4707 LIME & SHALE
4707 - 4721 LIME
4721 - 4810 LIME W/CHERT
4810 - 4860 LIME T.D.

GEOLOGICAL TOPS

LANSING 4242-4252
CHEROKEE 4563-4575
MISS CHERT 4585-4608
KINDERHOOK 4612-4624
VIOLA DOLM 4716-4726

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1962

CONSERVATION DIVISION
Wichita, Kansas

I, JAMES R. CRAIG, OF PAWNEE PETROLEUM COMPANY, INC., DO HEREBY CERTIFY THE ABOVE LOG TO BE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE.

James R. Craig
JAMES R. CRAIG

SUBSCRIBED AND SWORN TO BEFORE ME,
A NOTARY PUBLIC IN AND FOR SEDGWICK COUNTY, KANSAS, THIS 22 DAY OF DECEMBER, 1961.

Ralph E. Arbogast
RALPH E. ARBOGAST

MY COMMISSION EXPIRES 9-15-62