

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County, Sec. 26 Twp. 27 Rge. 16 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C NW NE  
Lease Owner Bowers Drilling Company, Inc.  
Lease Name Kenny Estate Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 11-28-62 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 12-5-62 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. XXXXXXX H. Justus  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4725 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	257'	None
				4-1/2"	4650'	2602'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 4725', sanded to 4570' and dumped 3 sacks of cement @ 4570' with dump bailer. Pulled 4 1/2" casing. Bailed fluid to 200', set rock bridge to 190' and ran 20 sacks of cement @ 190'. Mudded to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 14 1962

12-14-62  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of December, 19 62

My commission expires May 20, 1964  
Milton J. Volin Notary Public.



WELL LOG

COMPANY: Bowers Drilling Company, Inc.  
 CONTRACTOR: Bowers Drilling Company, Inc.  
 FARM: Kinney Estate #1  
 LOCATION: C S/2 NW NE Section 26-27S-16W  
 Kiowa County, Kansas

COMMENCED: 10-1-62  
 COMPLETED: 10-16-62  
 ELEVATION: 2087 K. B.

0 - 185 Clay and sand  
 185 - 490 Shale  
 490 - 995 Shale - redbed  
 995 - 1450 Shale  
 1450 - 1830 Shale and shells  
 1830 - 3958 Lime and Shale  
 3958 - 4035 Lime  
 4035 - 4198 Lime and Shale  
 4198 - 4470 Lime  
 4470 - 4532 Lime and shale  
 4532 - 4585 Lime  
 4585 - 4610 Lime and chert  
 4610 - 4635 Chert  
 4635 - 4698 Chert-sand  
 4698 - 4725 Viola  
 4725 T. D.

RECEIVED  
 STATE CORPORATION COMMISSION

FEB 25 1963

CONSERVATION DIV.  
 WICHITA, KANSAS

8-5/8" casing set at 357'  
 with 300 sacks

4 1/2" casing set at 4650' with  
 100 sacks

LOG TOPS:

Heebner Shale	3922	Marmaton	4432	Kinderhook Sand	4652
Brown Lime	4080	Cherokee Group	4542	Viola	4698
Lansing Lime	4098	Cherokee Sand	4565		
Base K.C. Lime	4416	Miss. Chert	4594		

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the copy of the log of the Kinney Estate #1, C S/2 NW NE Section 26-27S-16W, Kiowa County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

*Emil E. Bowers*  
 Emil E. Bowers

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this \_\_\_\_\_ day of \_\_\_\_\_, 196\_\_.

Donna F. Miller, Notary Public

My commission expires May 1, 1966.