

1 040854

6-9

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,285-00-60
C NW SE, SEC. 31, T 29 S, R 13 W/X
1980 1650 feet from S section line
1980 1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5290
Operator: Hinkle Oil Company
Name & Address: 150 N. Main, Ste. 1016
Wichita, KS 67202

Lease Name Larrison Well # 1
County Pratt
Well Total Depth 4775 155.18 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 247

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10:30 a.m. Day: 9 Month: 6 Year: 19 94

Plugging proposal received from Kenny Gates
(company name) Pratt Well Service (phone) 316-672-5901

Logs: 5 1/2" at 4774' w/150 sx cement, CIBP 4690', Perfs at 4654-57, 4734-36, 4739-41'

1st plug set CIBP at 4600' and dump 2 sx cement on top,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 2 sx hulls and 175 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 11:15 a.m. Day: 9 Month: 6 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4600' and dumped 2 sx cement on top through
bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50. sx cement, 10 sx
gel, 200 lbs. hulls and 175 sx cement.

Maximum pressure 600 psi and shut in 200 psi.

6-15-94

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3014' of 5 1/2" casing.
If additional description is necessary, use BACK of this form. observe this plugging.

INVOICED

DATE 6-20-94
INV. NO. 40582
6-9

Signed Stephen J. P... JUN 15 1994
(TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas

06-15-94