

6-14-88

1 040125

API NUMBER 15-151-20,476 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C S/2 SW NE, SEC. 31, T 29 S, R 13 W/8
2970 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5290

Lease Name Lambert Well # 1

Operator Name: Hinkle Oil Company

County Pratt 154.28

Address 1016 Union Center

Well Total Depth 4747 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 242

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 1 p.m. Day: 14 Month: 6 Year: 19 88

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 4611' PBDT 4538' Perfs at 4469-73'

1st plug sand back to 50' above perfs and dump 4 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 10 3/4"
wiper plug and pump 130 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:30 p.m. Day: 14 Month: 6 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 4404' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped down 10 3/4" with 400 lbs! hulls, 10 sx gel, 20 sx cement, 10 sx gel, 100 lbs. hulls and 130 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
06-22-88
JUN 22 1988

Maximum pressure 400 psi and shut in 325 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 3606' of casing.
(If additional description is necessary, use BACK of this form.)

INVOLVED

DATE 6-29-88

INV. NO. 21121

Signed Stephen J. Pfeifer (TECHNICIAN)