

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151 - 21,386 - 00-00
SE NE SW, Sec. 31, T 29 S, R 12 W/E
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5601

Lease Name Larrison Well # 1A

Operator: Associated Petroleum Consult.
Name & Suite 600 - One Main Place
Address Wichita, KS 67202

County Pratt

Well Total Depth 4780 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 379'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Bergman Drilling Company License Number 5659

Address 520 Union Center, Wichita, KS 67202

Company to plug at: Hour: 11:00 pm Day: 17 Month: January Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Jerry Hicks

(company name) Bergman Drilling (phone) 316-267-5291

were: to fill hole with heavy mud and spot cement through drill pipe. 1st plug at 4700 with 50 sx cement, 2nd plug at 1600' with 50 sx cement, 3rd plug at 800' with 50 sx cement, 4th plug at 430' with 40 sx cement. 5th plug - solid bridge at 40' to surface with 10 sx cement. 15 sx cement in rathole and plugged water well with 5 sx cement.

Signed Richard M. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:00 am Day: 18 Month: January Year: 1984

ACTUAL PLUGGING REPORT to fill hole with heavy mud and spot cement through drill pipe. 1st plug at 4700' with 50 sx cement, 2nd plug at 1600' with 50 sx cement. 3rd plug at 800' with 50 sx cement. 4th plug at 430' with 40 sx cement. 5th plug - solid bridge with 1/2 sack hulls and rubber plug at 40' and filled hole to surface with 10 sx cement. 15 sx cement in rathole and plugged water well with 5 sx cement.

Remarks: Halliburton accomplished the cementing with 60/40 Poz with 2% gel and 3% cc.

Ticket Number 581259

I hereby certify that the above plugging instructions were given as herein stated and that I (~~XXXX~~/ did not) observe this plugging.

INVOICED

DATE 1-25-84 RECEIVED
STATE CORPORATION COMMISSION

INV. NO. 9244-W
JAN 23 1984

Signed Richard M. Lacey
(TECHNICIAN)