

1 080057

3-26

167 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 13-151-21,985-0000

NW1/4, SEC. 31, T 29 S, R 13 W/E

4620 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Doris Lambert Well # 1-31

Operator: F.G. Holl Company

County Pratt 157.01

Name & Address P.O. Box 780167

Well Total Depth 4831 feet

Wichita, Ks 67278

Conductor Pipe: Size 13 3/8 feet 111

Surface Casing: Size ~~12 1/8~~ 8 3/8 feet 1139

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Trans-Pac Drilling, Inc. License Number 5841

Address One Main Place, Suite 410 Wichita Ks 67202

Company to plug at: Hour: 9:30 pm Day: 26 Month: 3 Year: 19 90

Plugging proposal received from Gary Pugh

(company name) Trans-Pac Drilling, Inc (phone) 262-3596

work: Spot a 50 sack plug at 1160, 40 sacks at 520, and fill from 40 to 0 with 10 sacks, 15 in rat hole, 10 sacks in mouse hole.

Plugging Proposal Received by Steve Dumant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 Day: 26 Month: 3 Year: 19 90

ACTUAL PLUGGING REPORT Spot plugs with drill pipe one at 1160' with 50 sacks, one at 520' with 40 sacks, fill from 40 to 0 with 10 sacks, put 15 sacks in rat hole and 10 sacks in mouse hole

Remarks: Used 60/40 Pozmix 6% gell by Halliburton (no casing set)
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-5-90

INV. NO. 27786

MAY 24 1990

3-26

Signed Mike Spain
(TECHNICIAN)