

2-070827

Docket: # D-26,930

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

6-11

016

API NUMBER: 15-095-01, ~~15-0001~~

NW NW , SECTION 8 TOWNSHIP 27S RANGE 9 W

OPERATOR LICENSE # 30931

4950 FEET FROM S SECTION LINE

OPERATOR Daystar Petroleum, Inc.

4950 FEET FROM E SECTION LINE

NAME & 1321 W. 93<sup>rd</sup> North

ADDRESS Valley Center, Ks. 67147

LEASE NAME: Sale # 1

COUNTY: Kingman

WELL TOTAL DEPTH: 4604

PIPE: 5 1/2" - 4449

SURFACE CASING: 8 5/8" - 311

149.63

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD XX D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Clarke Corp

ADDRESS: PO Box 187, Medicine Lodge, Ks. 67104 LICENSE: 5105

COMPANY TO PLUG AT: HOUR: 11:00a.m. DAY: 11th MONTH: June YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM: Mark

COMPANY NAME: Clarke Corp PHONE: 1-800-371-1634

WERE: CIBP - 4060

Sand to 3937- 5 sacks

35 sacks 1250

35 sacks 800

155 sacks 363 to 0

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 18 1999  
CONSERVATION DIVISION  
WICHITA, KS

PLUGGING PROPOSAL RECEIVED BY: Jack Luthi

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (XX) PART ( ) NONE ( )

COMPLETED: HOUR: 4:00p.m. DAY: 11th MONTH: June YEAR: 1999

ACTUAL PLUGGING REPORT: Set CIBP @ 4060'. Sand to 3937 and 5 sacks of comon.  
Shot 5 1/2" casing off at 2600' laid it out. Ran tubing to 1250  
pumped 35 sacks. Pulled to 800', pumped 35 sacks. Pulled to 363'  
and pumped 155 sacks to surface. Topped off with 10 sacks

REMARKS: Acid # 00823 60/40 4 \$

I DID OBSERVE THIS PLUGGING.  
Jack Luthi  
Jack Luthi

FORM CP-2/3  
REV. 3/90

PIRT **INVOICED**  
DATE 6-21-99  
INV. NO. 61076