

8-3

To: 1 040685  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Spud date 8/10/61  
C SE SW, SEC. 33, T. 27 S, R. 16 W/R  
660 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5118  
Operator: TGT Petroleum Corporation  
Name & Address: 209 E. William, Suite 615  
Wichita, KS 67202

Lease Name Davis Well R-1  
County Kiowa 154.86  
Well Total Depth 4765 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 10 a.m. Day: 3 Month: 8 Year: 19 92

Plugging proposal received from Eldon Folmsbee  
(company name) TGT Petroleum Corp. (phone) 316-262-6489

were: 4 1/2" at 4763' w/125 sx cement, PBD 4740', Perfs at 4735-40, 4743-48, 4703-05'  
1st plug sand back to 4650' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 3 Month: 8 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4610' and dumped 4 sx cement on top of sand  
bridge through badler,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 150 sx cement.

Maximum pressure 750 psi and shut in 400 psi.

RECEIVED STATE CORPORATION COMMISSION

8-13-92

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2520' of 4 1/2" casing  
(if additional description is necessary, use BACK of this report)

AUG 13 1992

INVOICED  
I did not observe this plugging.

DATE 9-11-92

Signed Stephen J. Pfeifer (TECHNICIAN)

WV. NO. 36092