

1030290

15-097-30138-0000

4-25-66

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Not available

C NW SW, SEC. 33, T 27 S, R 16 W/E
1980 feet from N SE Corner of
4620 feet from W SE Corner of
XXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5118

Lease Name Davis "R" Well # 2

Operator: TGT Petroleum Corp.
Name & Address 209 East William
Wichita, KS 67202

County Kiowa

Well Total Depth 4728 153.66 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 375

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor TGT Petroleum Corp. License Number 5118

Address 209 East William, Wichita, KS 67202

Company to plug at: Hour: 9:00 am Day: 28 Month: September Year: 19 84

Plugging proposal received from Mark Danner

(company name): TGT (phone) 316-262-6489

were: 4 1/2" set at 4720' Open Hole

Pump through tubing frac sand and 25 sx cement at 4650'. Trip out of hole and push

2 Hawco plugs to 1200', spot 25 sx cement and shut down over night.

Next day - fill 4 1/2" with cement (100 sx) and pump down annulus with 100 sx cement and shut in.

Plugging Proposal Received by Steve Danner (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:00 pm Day: 28 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4720' Open Hole

Spot frac sand and 25 sx cement at 4650'..Trip out and push plug to 740'. Circulated hole with cement to surface. Pumped down annulus with 100 sx cement and shut in.

Cement fell 700' in 4 1/2". Filled with Redi-mix.

STATE CORPORATION COMMISSION

OCT 09 1984

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc & Redi-mix by Halliburton.

(if additional description is necessary, use BACK of this form.) 10-9-84

(did / observe this plugging.)

Signed Steve Danner (TECHNICIAN)

INVOICED

DATE 10-11-84

INV. NO. 4245928

NOV 13 1984