

1 040044

1-29-88 15-097-30137-0000 193

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 5-23-66

C. NW NW, SEC. 33, T. 27 S, R. 16 W/X
4620 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414

Lease Name Davis Well # 2

Operator: J. Mark Richardson
Name & Address: 640 Century Plaza Bldg.
Wichita, KS 67202

County Kiowa 158.08

Well Total Depth 4864 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 274

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Greensburg Well Service License Number 5414

Address 303 East Kansas, Greensburg, KS 67054

Company to plug at: Hour: 1:30 p.m. Day: 29 Month: 1 Year: 19 88

Plugging proposal received from Carl Schield

(company name) Greensburg Well Service (phone) 316-862-5979

were: 4 1/2" at 4800' PBTD 3200' Perfs at 3160-65, 3173-95'

1st plug sand back to 3110' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 p.m. Day: 29 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3110' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 100 lbs. hulls and 125 sx cement.

Plate welded in top of 8 5/8" with 2" collar.

Maximum pressure 500 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1940' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.) Observe this plugging.

DATE 2-4-88
INV. NO. 19728

Signed Stephen J. Pfeifer (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION FEB 03 1988 CONSERVATION DIVISION Wichita, Kansas