

1 051034

4-8-88

15-097-30101-000 3910

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 11/14/65

C SW NW, SEC. 33, T 27 S, R 16 W Ex
33000 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414

Lease Name Davis Well # 1

Operator: J. Mark Richardson

County Kiowa 154.34

Name & Address 640 Century Plaza Building

Well Total Depth 4749 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 270

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Greensburg Well Service License Number _____

Address 303 East Kansas, Box 632, Greensburg, KS 67054

Company to plug at: Hour: 9:30 a.m. Day: 8 Month: 4 Year: 19 88

Plugging proposal received from Carl Schield

(company name) J. Mark Richardson (phone) 316-862-5979

were: 4 1/2" at 4749' PBD 4719' Perfs at 4708-09, 4634-54'

1st plug sand back 50' above perfs and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 8 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sand back to 4584' and dump 4 sx cement on top of sand

through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 150 sx cement.

Maximum pressure 300 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1820' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

RECEIVED STATE CORPORATION COMMISSION

4-13-88 APR 13 1988

INVOICED

Signed Richard W. Lacy (TECHNICIAN)

DATE 4-21-88

INV. NO. 20398 AUG 3 1988