

1 030827

JUN 27 1987

API NUMBER 15-097-21,242-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C. NW NW, SEC. 34, T. 27 S, R. 16 W/EX

4620 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3153

Lease Name Clark Well # 34-1

Operator: Cardwell & Parker

County Kiowa 154.57

Name & Address P.O. Box 1721

Well Total Depth 4756 feet

Plano, TX 75074

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 382

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor H-30, Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 10:30 a.m. Day: 27 Month: 6 Year: 19 87

Plugging proposal received from Jack Dunham

(company name) H-30, Inc. (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1023'

1st plug at base Anhydrite with 50 sx cement,

2nd plug at 30' below base of surface pipe with 40 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:30 a.m. Day: 27 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1023' with 50 sx cement,

2nd plug at 410' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 30 1987

6-30-87
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED
Please advise (if not) observe this plugging.

DATE 7-1-87

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 17382

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... 6 19 87 month day year

API Number 15-097-26242

OPERATOR: License # 3153 Name Cardwell & Parker Address P. O. Box 1721 City/State/Zip Plano, Texas 75074 Contact Person Ken Fletcher Phone (214) 422-1496

C. NW. NW Sec 34 Twp. 27 S. Rg. 16 E. West 4620' Ft. from South Line of Section 4620' Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 660 feet County Kiowa Lease Name Clark Well 34-1 Ground surface elevation 2120 (est.) feet MSI Domestic well within 390 feet yes X no Municipal well within one mile yes X no Depth to bottom of fresh water 200' Depth to bottom of usable water 200' 230 Surface pipe by Alternate 1 X 2 Surface pipe planned to be set 350' Conductor pipe required Projected Total Depth 4800 feet Formation Kinderhook

CONTRACTOR: License # 5107 Name H-30, Wichita, Kansas City/State Wichita, Kansas Well Drilled For: Oil Storage Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 6-11-87 Signature of Operator or Agent Ken Fletcher Title Agent

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 250 feet per Alt. This Authorization Expires 12-15-87 Approved By 6-15-87

Spud 6-20-87

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays)

Table with 3 columns: Plug depth (ft), Formation, and Plug material. Includes entries for 1st, 2nd, 3rd, 4th, and 5th plugs, with materials like 50 sks, 50/50 Poz 6% gel, Rat hole, and Mouse hole.

Log entries including: Pusher Jack D. Wine, TD 4756 FORMATION Hole, SURFACE PIPE 8 7/8 @ 3 1/2" ANHYDRITE 1023 ELEVATION 6-27-87, COMPLETION TIME & DATE 6-27-87 11:30AM, BASE Any w 50SX, 1st PLUG @ 1023 FT. W/ 50 SX, 2nd PLUG @ 410 FT. W/ 40SX, 3rd PLUG @ 40 FT. W/ 10 SX, 4th PLUG @ FT. W/ SX, RAT HOLE CIRCULATED W/ 15, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ Top 5' w/ gopher, CEMENT COMPANY Allied, TECHNICIAN Stone, dated 6/40/87.

RECEIVED STATE COMMISSION JUN 30 1987 CONSERVATION DIVISION Wichita, Kansas