

1 060191

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,998-0000

C SE SW, SEC. 34, T 27 S, R 16 W/X

660 feet from ~~W/S~~ section line

1980 feet from ~~W/S~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5021

Lease Name Fruit Well # 1-34

Operator: Imperial Oil Company

County Kiowa

Name & Address 720 Fourth Financial

Well Total Depth 4765 154.86 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 433

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 9:00 am Day: 2 Month: March Year: 19 84

Plugging proposal received from Mike Rempe

(company name) Red Tiger (phone) 316-263-2371

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1020' with 50 sx cement

2nd plug at 480' with 50 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement

Plug water well with 5 sx cement

Plugging Proposal Received by Paul A. Luthis (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:20 pm Day: 2 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1020' with 50 sx cement, 2nd plug at 480' with 50 sx

cement, 3rd plug & 4th plug - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rathole with 15sx cement. Plug water well with 5 sx

cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description necessary, use BACK of this form.)

RECEIVED

STATE CORPORATION COMMISSION

MAR 07 1984

Signed Paul A. Luthis (TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 01-84

INVOICED

DATE 3-12-84

INV. NO. 01076 3-2