

1 040324

9-26

144 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-097-21,180-0000  
NW NE NE, SEC. 34, T 27 S, R 16 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5943  
Operator: Boger Brothers Drilling, Inc.  
Name & Address P.O. Box 723  
Great Bend, KS 67530

4930 feet from S section line  
810 feet from E section line  
Lease Name RG Harper Well # 1  
County Kiowa 160.32  
Well Total Depth 4933 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 390

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Boger Brothers Drilling, Inc. License Number 5943  
Address P.O. Box 723, Great Bend, KS 67530

Company to plug at: Hour: 1:30 p.m. Day: 26 Month: 9 Year: 1989

Plugging proposal received from Mark Boger  
(company name) Boger Brothers Drilling, Inc. (phone) 316-792-8151

were: 5 1/2" at 4930' Perfs at 4658-68'

1st plug sand back to 4608' and dump 5 sx cement on top of sand through bailer,  
On 3/30/89, Kelso Casing Pulling had plugged bottoms and pulled casing. They attempted to  
plug down the 8 5/8" surface pipe pumping 400 lbs. hulls, 10 sx gel, 50 sx cement. They  
pumped a hole in the surface casing. On 9/25/89, Boger Brothers moved in a rig and washed  
down to re-plug.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 26 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4600' and dumped 5 sx cement on top of  
sand bridge with bailer. (Kelso Casing Pulling on 3/30/89)

9/26/89: Spotted plugs through 2 7/8" tubing. Ran gel spacer between plugs.  
2nd plug pumped 50 sx cement at 1120',  
3rd plug pumped 50 sx cement at 420',  
4th plug pumped 10 sx cement at 40'.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 5 1/2" casing  
(If additional description is necessary, use BACK of this form.)

(1010/1010) observe this plugging.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 28 1989  
9-29-89  
CONSERVATION DIVISION  
KANSAS

INVOICED  
DATE 10-3-89  
INV. NO. 26010  
9-26

Signed Stephen J. Pfeifer  
(TECHNICIAN)

NOV 06 1989