

1 120015

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C N/2 NE NW SEC. 35, T 27 S, R 16 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-09Z-21; 139-0000

4950 FEET FROM N/S SECTION LINE

3355 FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 9158

LEASE NAME November WELL # 1

OPERATOR: Case Oil & Gas, Inc.
NAME &
ADDRESS 110 S. Main

COUNTY Kiowa 158.60

Pratt, KS 67124

WELL TOTAL DEPTH 4880 Kinderhook FEET

CONDUCTOR PIPE: SIZE FEET

SURFACE CASING: SIZE 8 5/8" FEET 400'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D&A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR Aldebaran Drilling Co. Inc. LICENSE NUMBER 5829

ADDRESS 453 S. Webb Road, Suite 100, Box 18611 Wichita Ks 67207

COMPANY TO PLUG AT: HOUR: 1:00 pm DAY: 1 MONTH: June YEAR: 1985

PLUGGING PROPOSAL RECEIVED FROM Mark Guinn

(COMPANY NAME) Aldebaran Drilling Co Inc. (PHONE) 316-672-7471

WERE: Keep Hole full of good drilling mud and spot all plugs through open ended drill pipe. 1st plug at 1270' with 40 sx of cement. 2nd plug at 600' with 40 sx of cement. 3rd plug at 450' with 30 sx of cement. 4th plug at 40' build a solid bridge with 1 sx of hulls and a 8 5/8" wiper plug and fill Hole to surface w/10 sx Use 50/50 pozmix for all of the plugs. Circulate the rat hole w/15sx. Circulate mousehole w/10 sx. PLUGGING PROPOSAL RECEIVED BY Don Ubel (TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 4:30 DAY: 1 MONTH: June YEAR: 1985

ACTUAL PLUGGING REPORT Kept hole full of good drilling mud and spotted all plugs through open ended drill pipe. 1st plug at 1270' with 40 sx of cement. 2nd plug at 600' with 40 sx of cement. 3rd plug at 450' with 30 sx of cement. 4th plug at 40' built a solid bridge with 1 sx of hulls and a 8 5/8" wiper plug and filled hole to surface w/10 sx circulated the rat hole with 10 sx. Circulated the mouse hole with 10 sx. Used 50/50 pozmix 6% gel 2% cc cement for all plugs RECEIVED STATE CORPORATION COMMISSION JUN 07 1985

REMARKS: Sun cementing pumped all the cement Anhydrite was at 1260' to 1290' CONSERVATION DIVISION Wichita, Kansas

I (BY / DID NOT) OBSERVE THIS PLUGGING.

SIGNED *Don C. Ubel* (TECHNICIAN)

INVOICED

DATE 6-18-85

INV. NO. 8538

FORM CP-2/3 REV. 6-83