

To: 1051908 3-16
STATE CORPORATION COMMISSION
Wichita State Office Bldg. **PLUGGING SECTION**
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-097-20,734-0000
NE NE NE, SEC. 27, T. 27 S, R. 16 ~~W&K~~
4950 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5414
Operator: J. Mark Richardson
Name: _____
Address: 155 N. Market, Ste. 830
Wichita, KS 67202

Lease Name Harper Well # 2
County Kiowa 151.29
Well Total Depth 4655 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 415

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Greensburg Well Service License Number 31201
Address: 155 N. Market, Ste. 830, Wichita, KS 67202

Company to plug at: Hour: 10 a.m. Day: 16 Month: 3 Year: 19 95

Plugging proposal received from Carl Schield
(company name) Greensburg Well Service (phone) 316-723-2204

Work: 4 1/2" at 4652' w/150 sx cement, PBTD 4646', Perfs at 4590-4600, 4630-46', BP. at 4620'
1st plug set CIBP at 4120' with 1 sx cement on top,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 16 Month: 3 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4120' and dumped 1 sx cement on top,
2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx
hulls, released 8 5/8" wiper plug and pumped 150 sx cement.
Maximum pressure 500 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2320' of 4 1/2" casing.

INVOICED
I (did / ~~did not~~) observe this plugging.

DATE 3-30-95

INV. NO. 42496

Signed Richard W. Lyon
(TECHNICIAN)

3-16 JUN 21 1995

STATE CORPORATION COMMISSION
RECEIVED
MAP 2
CONSOLIDATED
JUN 21 1995