

1 040783 9-17

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-097-20,524A  
C NW NE, SEC. 27, T 27 S, R 16 W/R  
4620 feet from S section line  
1980 feet from E section line  
Lease Name Harper Well # 1  
County Kiowa  
Well Total Depth 4656 151.32 feet

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414  
Operator: J. Mark Richardson  
Name & Address 155 N. Market, Ste. 830  
Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 365

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor J. Mark Richardson License Number 5414  
Address 155 N. Market, Ste. 830, Wichita, KS 67202

Company to plug at: Hour: 2 p.m. Day: 17 Month: 9 Year: 19 93

Plugging proposal received from Carl Schield  
(company name) J. Mark Richardson (phone) 316-723-2204

Work: 4 1/2" at 4654' w/200 sx cement, PBDT 4640', Perfs at 4561-67, 4604-14, 4648-53!  
1st plug sand back to 4500' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 2:45 p.m. Day: 17 Month: 9 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4500' and dumped 4 sx cement on top of sand bridge through bailer,  
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.  
Maximum pressure 500 psi and shut in 200 psi.

9-22-95

RECEIVED STATE CORPORATION COMMISSION SEP 22 1995

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3510' of 4 1/2" casing.  
If additional description is necessary, use BACK of this form.

INVOICED

DATE OCT 05 1993

INV. NO. 38879 9-17

Signed Stephen J. Pfeifer (TECHNICIAN) CONSERVATION DIVISION Wichita, Kansas