

1-24

To: 1 061180
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,054-0000
C SW SW, SEC. 27, T 27 S, R 16 W
660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414
Operator: J. Mark Richardson
Name & Address: 111 West Douglas, Suite 640
Wichita, KS 67202

Lease Name White Well # 1
County Kiowa 155.03
Well Total Depth 4770 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 278

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Greensburg Well Service License Number _____

Address _____

Company to plug at: Hour: 11:30 a.m. Day: 24 Month: 1 Year: 19 89

Plugging proposal received from Carl Schield

(company name) J. Mark Richardson (phone) 316-723-2204

were: 4 1/2" at 4765' PBSD 4685' Perfs at 4644-78', 4601-11'

1st plug set CIBP at 3120' and dump 2 sx cement on top of sand, 2nd plug pump 2 sx hulls, 10 sx gel, 50 sx cement; 10 sx gel, 1 sx hulls and 120 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 25 1989

1-25-89

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations Observed by Agent?: All Part _____ None _____

Operations Observed at: Hour: 12:15 p.m. Day: 24 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3120' and dump 2 sx cement on top, 2nd plug pumped 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 120 sx cement.

Maximum pressure 650 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2100' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

DATE 1-27-89

INV. NO. 23806

1-24