

1052014

13-011-30135-000

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Spud Date 2/5/66
C NE SE, SEC. 32, T 27 S, R 16 W
1980 feet from S section line
660 feet from E section line

2-14

TECHNICIAN'S PLUGGING REPORT
Operator License # 5414
Operator: J. Mark Richardson
Name & Address: 155 N. Market, #840
Wichita, KS 67202

Lease Name Woodard Well # 1
County Kiowa 152.98
Well Total Depth 4707 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 282

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Greensburg Well Service License Number 31201
Address: 303 E. Kansas, Greensburg, KS 67054

Company to plug at: Hour: 9:30 a.m. Day: 14 Month: 2 Year: 1996

Plugging proposal received from Carl Schield
(company name) Greensburg Well Service (phone) 316-723-2204

Work: 4 1/2" at 4692' w/200 sx cement, PBTD 4680', Perfs at 4642-68', 4704-4716'
1st plug sand back to 4590' and dump 4 sx cement on top of sand through bailer,
2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 10:15 a.m. Day: 14 Month: 2 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 4590' and dumped 4 sx cement on top of sand
through bailer,
2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100
lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.
Maximum pressure 250 psi and shut in 100 psi.

2-19-96

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2375' of 4 1/2" casing
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 2-28-96

INV. NO. 44905

Signed Richard W. Jurek
(TECHNICIAN)

RECEIVED
KANSAS CORP
COMM
1996 FEB 19 5:39 PM