

1 060664

Docket No. E-14,550  
Comp. 6-4-66

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- \_\_\_\_\_  
C SW NE \_\_\_\_\_, SEC. 32, T 27 S, R 16 W/E  
3300 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414

Lease Name Isham Well # 1

Operator: J. Mark Richardson  
Name & Address 640 Century Plaza Building  
Wichita, KS 67202

County Kiowa 152.75

Well Total Depth 4700 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 274

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well X D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893

Address P. O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 8:45 am Day: 24 Month: September Year: 19 85

Plugging proposal received from Carl Shields

(company name) J. Mark Richardson (phone) 316-262-3192

were: 4 1/2" at 4699' Perfs at 4637-49'

1st plug pump down 4 1/2" 2 sx hulls, 50 sx cement, 18 sx gel, and 70 sx cement

2nd plug pump 200 sx cement down 8 5/8"

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:10 am Day: 24 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing - 2 sx hulls, 50 sx cement, 18 sx gel, released 8 5/8" rubber plug and pumped 70 sx cement.

Maximum pressure 300 psi and shut in 200 psi

2nd plug pumped 200 sx cement down 8 5/8"

Maximum pressure 300 psi and shut in 200 psi

Remarks: No recovery. Used 60/40 Pozmix 6% gel by Halliburton  
(if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED STATE CORPORATION COMMISSION

Signed Paul A. Lutter (TECHNICIAN)

DATE OCT 03 1985

INV. NO. 10336

SEP 27 1985

9-27-85

OCT 23 1985 CONSERVATION DIVISION