

1 060027

6-26

15-097-20733-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-24,507
SE SE SW, SEC. 22, T 27 S, R 16 W/EX

TECHNICIAN'S PLUGGING REPORT

330 feet from S section line
2970 feet from E section line

Operator License # 5414

Lease Name Clark Well # A-1

Operator: J. Mark Richardson

County Kiowa 152.13

Name & Address 155 N. Market, #840

Well Total Depth 4681 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 401

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Greensburg Well Service License Number _____

Address Greensburg, KS

Company to plug at: Hour: 4 p.m. Day: 26 Month: 6 Year: 19 90

Plugging proposal received from Carl Schield

(company name) J. Mark Richardson (phone) 316-723-2204

were: 4 1/2" at 4680', PBSD 4676', Perfs at 4658-62, 4552-60, 4586-96, 4312-18, 4082-86'

1st plug sand back to 4030' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 7 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 5:30 p.m. Day: 26 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4030' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 7 sx gel, 100 lbs. hulls, and 125 sx cement.

Maximum pressure 700 psi and shut in 400 psi.

RECEIVED
STATE CORPORATION COMMISSION
JUN 28 1990
CONSERVATION DIVISION
WICHITA, KANSAS

6-28-90

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2320' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (do not observe this plugging.)

DATE 7-3-90

Signed Carl M... (TECHNICIAN)

INV. NO. 28540

6-26