

11-9

1 040186

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-20,422-0000

C SE NW, SEC. 23, T 27 S, R 16 W/E

3300 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Fankhauser "A" Well # 1

Operator: TXO Production Corporation

County Kiowa 152.69

Name & Address 155 North Market, Suite 1000

Well Total Depth 4698 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 336

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5015

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11:15 a.m. Day: 9 Month: 11 Year: 1988

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4696' PBD 4678' Perfs at 4620-24, 4638-42'

1st plug sand back to 4570' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

11-15-88

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed Hour: 11:45 a.m. Day: 9 Month: 11 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 4575' and dumped 4 sx cement on top of

sand through bailer,

2nd plug pumped down 8 5/8" with 200 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 700 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 2% gel, 2% cc, by B.J. Titan. Recovered 2550' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

and ~~observe~~ observe this plugging.

INVOICED

Signed Stephen J. Zieper
(TECHNICIAN)

DATE 11-21-88

INV. NO. 23053