

11-20-87

1040014

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill completion 12/22/77

SE SW, SEC. 18, T 27 S, R 16 W/E
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9339

Lease Name Davis Well # 2-18

Operator: K & K Oil Company

County Kiowa 153.40

Name & Address Box 176

Well Total Depth 4720 feet

Chase, KS 67524

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 403

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3:30 p.m. Day: 20 Month: 11 Year: 1987

Plugging proposal received from Clay Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4719' PBD 4706' Perfs at 4638-42' Elevation 2111' GL

1st plug pump 1 sx hulls and 20 sx cement,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release plug

and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4 p.m. Day: 20 Month: 11 Year: 1987

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 100 lbs hulls and 20 sx cement,

2nd plug pumped down 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50.sx cement,

10 sx gel, 100 lbs. hulls, released wiper plug and pumped 100 sx cement.

Pumping pressure 300-600 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2500' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION NOV 25 1987 CONSERVATION DIVISION Wichita, Kansas

(If ~~desired~~) observe this plugging.

INVOICED

Signed Stephen J. Pfeiffer (TECHNICIAN)

DATE 12-3-87

INV. NO. 19040