

1 090270

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-097-20,829-0000 *R*  
NE NE, SEC. 14, T 27 S, R 16 W/E

4620 feet from ~~W~~S section line  
660 feet from ~~W~~E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5028

Lease Name Clarkson Well # 1-14

Operator: Imperial Oil Co.

County Kiowa 150.64

Name & Address 720 Fourth Financial Center

Well Total Depth 4635' feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 407 ✓

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: noon Day: 3 Month: January Year: 19 85

Plugging proposal received from Bill Fulls

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4634' PBD 4120' Perfs at 4074-77', 4287-89', 4202-05'

1st plug sand back to 4020' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 120 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:00 pm Day: 3 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 4 1/2" set at 4634' PBD 4120' Perfs at 4074-77, 4287-89, 4202-05'

1st plug sanded back to 4020' and dumped 4 sx cement on top of sand through bailer

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 120 sx cement.

1-7-85

Maximum pressure 625 psi and shut in 100 psi RECEIVED STATE CORPORATION COMMISSION

Remarks: Recovered 3338' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 1-15-85

Signed *R. B. Farber* CONSERVATION DIVISION Wichita, Kansas (TECHNICIAN)

INV. NO. 6458