

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-01022-00-01  
Spot: SWNWNW Sec/Twnshp/Rge: 28-30S-7E  
4266 feet from S Section Line, 5085 feet from E Section Line  
Lease Name: SMITH Well #: 1  
County: COWLEY Total Vertical Depth: 3265 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	3213		
PROD	7	2838		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/14/2015 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JEFF KLOCK Company: KANSAS CORPORATION COMM Phone: (316) 630-4000

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/15/2015 9:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) PERFORATED CASING AT 350'. 2) RAN IN W/TUBING TO 3200' AND PUMPED 35 SKS OF 60/40 4% CEMENT. 3) PULLED TUBING UP TO 350' AND PUMPED 65 SKS CEMENT. CEMENT CIRCULATED UP CASING, NO CIRCULATION UP BACKSIDE. 4) DUG OUT AROUND WELL AND FOUND 7" CASING WITH CEMENT APPROX. 15' DOWN. FILLED REMAINING ANNULAR SPACE WITH CEMENT. 5) TOPPED OFF WITH 25 SKS CEMENT. CEMENT FALLING - TO BE TOPPED OFF NEXT DAY. 7/15/2015: PUMPED 75 SKS OF 60/40.4% CEMENT FOR TOP CUT, CIRCULATED TO AND STAYING AT SURFACE.

Perfs:

Top	Bot	Thru	Comments
3206	3208		CSG

Remarks: CEMENTING COMPLETED BY QUALITY WELL SERVICE, ELLINWOOD, KS. TICKET #6014. PLUGGED DUE TO COMMISSION ORDER.

Plugged through: TBG Control # 20150025-001

District: 02

Signed Jonathan Hill  
KCC WICHITA (TECHNICIAN)

AUG 03 2015

RECEIVED

JK