

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-23986-00-00
Spot: NESWNW Sec/Twnshp/Rge: 28-30S-7E
3810 feet from S Section Line, 4607 feet from E Section Line
Lease Name: SMITH Well #: 4
County: COWLEY Total Vertical Depth: 3217 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3215		200 SXS CMT
SURF	8.625	308		160 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/15/2015 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JEFF KLOCK Company: KANSAS CORPORATION COMM Phone: (316) 630-4000

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/15/2015 3:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) PERFORATED CASING AT 350'. 2) RAN IN W/TUBING TO 3100' AND PUMPED 35 SKS OF 60/40 4% CEMENT. 3) PULLED TUBING UP TO 350' AND PUMPED 95 SKS CEMENT, CIRCULATED TO SURFACE ON 5.5" CASING. 4) TRIPPED TUBING OUT, TIED IN TO 5.5" CASING AND PUMPED 30 SKS, CEMENT CIRCULATED UP BACKSIDE. 5) TOPPED OUT W/ 35 SKS, CEMENTED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3215	3217		CSG

Remarks: CEMENTING COMPLETED BY QUALITY WELL SERVICE, ELLINWOOD, KS. TICKET #6015. PLUGGED DUE TO COMMISSION ORDER.

Plugged through: TBG Control#20150025-003

District: 02

Signed Jonathan Hill

(TECHNICIAN)
KCC WICHITA

AUG 03 2015

RECEIVED