



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION

NOV 1 1973

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-081-10113-0000

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Mobil has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Mobil Oil Corporation

Complete Address: Box 1934, Oklahoma City, Oklahoma

Lease Name: Sprunger "A" Well No. 2

Location: C NW SE Sec. 20 Twp. 28 Rge. 34 XY (E) (W)

County: Haskell Total Depth 5550' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1909' circulated w/ cement. 5 1/2" to 5521' cemented.

Top perforations 5476' Plug bottom w/ 20 sacks cement.

Top of cement 5400' Mud 5400' to 1000'

Spotted 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Hulls " 15 sacks cement 45' to 0'.

Very truly yours,

Edward J. Eves
Conservation Division Agent