



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-681-00017-0000

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 17 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Schmidt of Mobil Oil Corp. has this

date requested permission to plug the following described well:

Mr. Schmidt guarantees payment of the plugging fee.

Operator's full Name: Mobil Oil Corporation

Complete Address: Box 1828, Oklahoma City, Oklahoma

Lease Name: Sprunger "C" Well No. 1

Location: C SE SW Sec. 20 Twp. 28 Rge. 34 (E) (W)

County: Haskell Total Depth 5460' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Schmidt was instructed to plug the well as follows:

8 5/8" to 1903' circulated w/ cement. 5 1/2" to 5445' cemented.

Top perforations 4709' Plug bottom w/ 25 sacks cement

Top of cement 4500' Mud 4500' to 1850'

Spot 35 sacks cement 1850' to 1750' Mud 1750' to 0'.

Weld Plate on 8 5/8" casing.

Very truly yours,

Edgar J. Lives
 Conservation Division Agent