



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-081-00027-0000

RECEIVED
STATE CORPORATION COMMISSION
NOV 5 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Mobil has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Mobil Oil Corporation

Complete Address: Box 1934, Oklahoma City, Oklahoma

Lease Name: Clark "C" Well No. 1

Location: C SE NE Sec. 20 Twp. 28 Rge. 34 XX (E) (W)

County: Haskell Total Depth 5652' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1886' circulated w/ cement. 5 1/2" casing to 5562' cemented

Top perforations 5335' Plug bottom w/ 20 sacks cement.

Top of cement 5250' Mud 5250' to 1000'

Spott 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent