

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-081-10108-0000

RECEIVED
STATE CORPORATION COMMISSION
NOV 7 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Norris of Mobil Oil Corp. has this

date requested permission to plug the following described well:

Mr. Norris guarantees payment of the plugging fee.

Operator's full Name: Mobil Oil Corporation

Complete Address: Box 1934, Oklahoma City, Oklahoma

Lease Name: Clark Well No. 2-C

Location: C NW NE Sec. 20 Twp. 28 Rge. 34 ~~(E)~~ (W)

County Haskell Total Depth 5628' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Norris was instructed to plug the well as follows:

8 5/8" to 1898' circulated w/ cement. 5 1/2" to 5432' cemented.

Top perforations 4522' Plug, bottom w/ 20 sacks cement.

Top of cement 4400' Mud 4400' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.2

Very truly yours,

Edgar J. Evers
Conservation Division Agent