

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-081 - 16063-0000

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Patterson of Graham-Michaelis has this  
date requested permission to plug the following described well:

Mr. Patterson guarantees payment of the plugging fee.

Operator's full Name: Graham-Michaelis Drilling Inc.

Complete Address: 211 North Broadway, Wichita, Kansas

Lease Name: Eubank "A" Well No. 2-23

Location: C SW SW Sec. 23 Twp. 28 Rge. 34 (W)

County Haskell Total Depth 5550' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Patterson was instructed to plug the well as follows:

8 5/8" to 857' circulated w/ cement. 4 1/2" to 4258' cemented.

Top perforations 4175' Plug bottom w/ 15 sacks cement

Top of cement 4000' Mud 4000' to 850'

Spotted 40 sacks cement 850' to 750' Mud 750' to 45'

Plug, Halls & 15 sacks cement 45' to 0'

RECEIVED  
STATE CORPORATION COMMISSION

SEP 26 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Very truly yours,

Edward J. Eves  
Conservation Division Agent