



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

15-081-10067-0000

RECEIVED
STATE CORPORATION COMMISSION

APR 27 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Sargent of Graham-Michaelis has this
 date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Graham-Michaelis

Complete Address: 211 North Broadway, Wichita, Kansas

Lease Name: Ubank "B" Well No. # 1-23

Location: C NW NE Sec. 23 Twp. 28S Rge. (E) (W) 34

County Haskell Total Depth 5606' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:


8 5/8" - 783' Circulated w/cement. 4 1/2" - 5450' Cemented. Perforations - 5213' - 5236'

Plug bottom w/20 Sax. cement top cement 5150' Mid 5150' to 700'

35 Sax. cement 700' to 600' Mid 600' to 45'

15 Sax. cement 45' to 0

Very truly yours,


 Conservation Division Agent