



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

15-081-10047-0000

RECEIVED  
STATE CORPORATION COMMISSION

JUL 9 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Mallonee of W.J. Coppinger has this  
 date requested permission to plug the following described well:

Mr. Mallonee guarantees payment of the plugging fee.

Operator's full Name: W.J. Coppinger

Complete Address: 717 Union Natl. Bldg. Wichita, Kansas

Lease Name: Doerksen Well No. # 1

Location: C NW NE Sec. 27 Twp. 28S Rge. 34 (E) (W)

County Haskell Total Depth 5633 Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Mallonee was instructed to plug the well as follows:

8 5/8" 758' Circulated w/cement.


Heavy Mud 5633' to 3000' Spotted 125 Sax. cement 3000' to 2532'

Heavy Mud 2532' to 700' Spotted 35 Sax. cement 700' to 575'

Heavy Mud 575' to 45' Plug 15 Sax. cement 45' to surface.

Weld Cap on surface, Halliburton Cementing Co.

Very truly yours,

  
 Conservation Division Agent